



Preliminary Stormwater Management Plan

for

Woodspring Suites Hotel

1744 County Road D
Maplewood, MN

Prepared By:

Andy Reinisch

Peter Moreau, PE

July 27, 2020



12800 Whitewater Drive, Suite 300
Minnetonka, MN 55343
2436 E Randol Mill Rd
Arlington, TX 76011

Contents

Project Introduction.....1

Soil Classification2

Existing Conditions.....2

Proposed Conditions3

Rate Control3

Water Quality.....4

Volume Reduction.....5

Emergency Overflow5

Stormwater System Operations & Maintenance5

Erosion & Sediment Control.....6

Summary.....6

Appendices

- Appendix A – Drainage Maps
- Appendix B – Web Soil Survey Results
- Appendix C – HydroCAD Calculations
- Appendix D – MIDS Calculations

PROJECT INTRODUCTION

The proposed project consists of the development of a 2.04-acre site located at 1744 County Road D (PID 032922110005) in Maplewood, Ramsey County, Minnesota. The site is within the Ramsey-Washington Metro Watershed District. The City of Maplewood & RWMWD are the permitting authorities for stormwater management. The proposed site consists of construction of a 4-story hotel and related parking lot & site utilities. Currently the site consists of a vacant & undeveloped grass lot surrounded by streets on all four sides. The net site area less right-of-way for the four streets is 1.68-acres.

Stormwater from the project will be collected into a subsurface infiltration & detention system. The system will outlet to the existing 15" pipe in the southwest corner and will discharge at peak rates meeting the approved allowable discharge rates for the Legacy Parkway master plan provided by City Engineering staff.

The project has been designed to meet the criteria provided by the Assistant City Engineer (Jon Jarosch) that states: "We would require that the proposed site would have its rate controlled such that it is equal to or less than 3.8 cfs for the 10-year storm event. The site will also still be required to meet the City's 1.1-inch over the site impervious volume reduction requirements."

The stormwater system has been designed to meet the following requirements.

- Volume control requirement - 1.1-inches over the site impervious (City of Maplewood and RWMWD)
- Water quality requirements – 90% TSS and 60% TP removals (City of Maplewood and RWMWD)
- Rate Control – Peak runoff rate from ten-year storm event is < 3.8 cfs per Legacy Parkway Master Plan (City of Maplewood, Jon Jarosch)

SOIL CLASSIFICATION

A geotechnical report for this site is forthcoming. Per the USDA Web Soil Survey results, the existing site consists of Chetek sandy loam and is classified as Hydrologic Soil Group A (HSG A). Based on this information, existing soils are suitable for infiltration. The web soil survey results also show no signs of shallow groundwater levels.

EXISTING CONDITIONS

The site currently consists of a vacant grassed lot with 0.01 acres impervious. There is no existing stormwater management on the site. There is an existing 15" storm sewer stub to the lot that was sized and planned for receiving runoff from this lot in developed conditions. The site is relatively flat with slopes ranging from 1%-4%. The site has a high point that splits into 3 directions; north, east and southwest. The majority of the site drains to the southwest corner where the existing public storm sewer collects at Flandrau Street & Village Trail. The public sewer ultimately discharges to the southwest.

Existing Areas & Curve Numbers

Subcatchment	Area	Weighted CN
E1	1.23	61
E2	0.33	61
E3	0.12	61
TOTAL	1.68	

PROPOSED CONDITIONS

The proposed site includes the construction of a 4-story hotel building with adjacent parking lots and 2 driveway access points. The proposed site will include a total of 1.42 acres of impervious, or a net increase of 1.41 acres from the existing conditions. The site drains to a series of catch basins that ultimately drain to an underground stormwater infiltration & detention system. Per the city of Maplewood standards, the existing 15" storm sewer pipe stubbed to the site was designed with the intention of allowing up to 3.8 cfs of peak stormwater discharge during the 10-year storm event for a future development at this site. Proposed drainage areas P7 and P8 will drain off-site and to the existing streets & public storm sewer similar to existing conditions (at rates less than existing conditions).

Proposed Areas & Curve Numbers

Subcatchment	Area	Weighted CN
P1	0.24	92
P2	0.29	92
P3	0.16	94
P4	0.31	92
P5	0.21	97
P6	0.29	98
P7	0.15	75
P8	0.03	61
TOTAL	1.68	

RATE CONTROL

As this site was developed and planned as part of a larger development (the Legacy Parkway PUD) the existing grass conditions of the site create very little runoff in the existing model. Therefore, proposed rates exceed predevelopment modeled rates but per the city of Maplewood's comments, they want the developed site to discharge into the provided 15" storm sewer stub as long as the peak discharge rate doesn't exceed 3.8 cfs in the 10-year event. The existing site drains to the north, east and southwest. In the proposed condition the area to the north is now being captured on-site and the area to the east was reduced significantly. The HydroCAD model is using the rainfall events from the County lookup table and MSE 24-hr Storm Curve 3. The existing time of

concentrations were determined using sheet flow. The proposed time of concentrations were determined using the MnDOT standard for minimum Tc for paved areas (7 minutes) as the areas are very small.

Design Rainfall Events

Storm Event	(in)
2-Year	2.81
10-Year	4.19
100-Year	7.36

Peak Rate of Runoff (cfs)

Storm Event	City Requirement	Proposed 10-yr Discharge
10-Year	3.80	2.33

PRETREATMENT

Pretreatment devices include sumps on the parking lot inlets. The inlets upstream of the system will be installed with a sump to remove initial larger sediments. The ADS StormTech Isolator Row will be the first row to collect runoff entering the systems to supplement pre-treatment removals.

WATER QUALITY

The city of Maplewood stormwater design standards require that the site BMP's achieve 90% total suspended solids (TSS) and 60% total phosphorus (TP) removals modeled on an annual basis.

The Ramsey-Washington Metro Watershed District requires that the site BMP's achieve 90% total suspended solids (TSS) removal from the disturbed area of the project on an annual basis and total phosphorus removals are inherited through the volume control policy.

These requirements will be met with the installation of the subsurface infiltration system. A MIDS analysis was completed to demonstrate compliance. A summary of the annual pollutant load removals for the proposed conditions can be found tabulated below. Please refer to Appendix D for the full results of the MIDS analysis.

Nutrient Analysis

BMP	TSS Removal (%)	TP Removal
Subsurface Infiltration BMP	97	97

VOLUME REDUCTION

The City of Maplewood & RWMWD require volume control of 1.1-inches over all new & reconstructed site impervious area. Since the site soils are conducive to infiltration, an infiltration rate of 0.8 ft/s was used in design since that is the recommended design infiltration rate for HSG A soils from the MN Stormwater Manual. A subsurface infiltration system has been designed to meet the volume reduction requirements. A summary of the infiltration calculations is tabulated below.

$$\text{Required Infiltration Volume}(ft^3) = V_{inf} = 1.1(in) * \frac{1 ft}{12 in} * \text{New Impervious Area} (ft^2)$$

$$V_{inf}(ft^3) = 1.1(in) * \frac{1 ft}{12 in} * 61,419(ft^2) = 5,630 ft^3$$

Volume Control Analysis

New Impervious Surface	61,419	sf
Design Infiltration/Filtration Rainfall Event	1.1	in
Required Infiltration/Filtration Volume	5,630	cf
Maximum Allowable Infiltration Rate	0.80	in/hr
Required Drawdown Time	48	hrs
Maximum depth to Outlet for Drawdown	3.2	ft
Provided Infiltration Depth below Outlet	2.5	ft
Provided Volume Below Outlet	7,010	cf

EMERGENCY OVERFLOW

The grading design will convey overflow runoff overland through the site should a catch basin or pipe become plugged, or if a rainfall event occurs that exceeds the design capacity of the storm sewer system. In the southwest corner of the site is the site's ultimate emergency overflow at elevation 925.42'. If the underground system were to back up, the site will still overland flow to the southwest into the existing public stormwater system at Flandrau Street & Village Trail. The 100-year high water level in the system is 924.17' which is 7.8' below the LFE of 932.00'. Freeboard requirements will be met.

STORMWATER SYSTEM OPERATIONS & MAINTENANCE

An operations and maintenance manual will be provided as part of the final design and as required by RWMWD & City of Maplewood.

EROSION & SEDIMENT CONTROL


A comprehensive Stormwater Pollution Prevention Plan (SWPPP) meeting the requirements of the 2018 MPCA NPDES permit will be developed as a part of the final plans.

SUMMARY

The proposed Woodspring Suites Hotel project will meet the requirements of the City of Maplewood, Ramsey-Washington Metro Watershed District, and MPCA through construction of an underground stormwater infiltration & detention system. This system will provide the required rate control, water quality, and volume reduction improvements prior to discharging stormwater runoff from the site to downstream receiving waters.

If you have any questions, comments, or additional information regarding this report, please contact me at Pmoreau@sambatek.com or (763) 398-0858.

APPENDIX A – Drainage maps



LEGEND



LINK



POND




REACH



SUB-CATCHMENT

* TC WAS DETERMINED USING THE MNDOT MINIMUM FOR PAVED PARKING LOT SHEET FLOW



12800 Whitewater Drive, Suite 300
Minnetonka, MN 55343
763.476.6010 telephone
763.476.8532 facsimile
Engineering | Surveying | Planning | Environmental

Client

SOTA
PARTNERS
Project
WOODSPRING
SUITES HOTEL

Location
1744 COUNTY
ROAD D

Certification

Summary

Approved: PSM Drawn: AIR

Revision History

No.	Date	By	Submittal / Rev.
-----	------	----	------------------

Sheet Title
PROPOSED
DRAINAGE MAP

Sheet No. Revision
2/2


Project No. 22163

APPENDIX B – Web Soil Survey

Soil Map—Ramsey County, Minnesota
(WSS Hotel in Maplewood)



Map Scale: 1:677 if printed on A landscape (11" x 8.5") sheet.




Natural Resources
Conservation Service

Web Soil Survey
National Cooperative Soil Survey

7/6/2020
Page 1 of 3


MAP LEGEND

Area of Interest (AOI)

 Area of Interest (AOI)

Soils

 Soil Map Unit Polygons

 Soil Map Unit Lines

 Soil Map Unit Points

Special Point Features



Blowout



Borrow Pit



Clay Spot



Closed Depression



Gravel Pit



Gravelly Spot



Landfill



Lava Flow



Marsh or swamp



Mine or Quarry



Miscellaneous Water



Perennial Water



Rock Outcrop



Saline Spot



Sandy Spot



Severely Eroded Spot



Sinkhole



Slide or Slip



Sodic Spot



Spoil Area



Stony Spot



Very Stony Spot



Wet Spot



Other



Special Line Features

Water Features



Streams and Canals

Transportation



Rails



Interstate Highways



US Routes



Major Roads



Local Roads

Background



Aerial Photography

MAP INFORMATION

The soil surveys that comprise your AOI were mapped at 1:15,800.

Warning: Soil Map may not be valid at this scale.

Enlargement of maps beyond the scale of mapping can cause misunderstanding of the detail of mapping and accuracy of soil line placement. The maps do not show the small areas of contrasting soils that could have been shown at a more detailed scale.

Please rely on the bar scale on each map sheet for map measurements.

Source of Map: Natural Resources Conservation Service

Web Soil Survey URL:

Coordinate System: Web Mercator (EPSG:3857)

Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts distance and area. A projection that preserves area, such as the Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required.

This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: Ramsey County, Minnesota

Survey Area Data: Version 15, Jun 5, 2020

Soil map units are labeled (as space allows) for map scales 1:50,000 or larger.

Date(s) aerial images were photographed: Aug 8, 2019—Aug 9, 2019

The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.

Map Unit Legend

Map Unit Symbol	Map Unit Name	Acres in AOI	Percent of AOI
155B	Chetek sandy loam, 0 to 6 percent slopes	1.8	77.0%
155C	Chetek sandy loam, 6 to 12 percent slopes	0.5	23.0%
Totals for Area of Interest		2.3	100.0%

Ramsey County, Minnesota

155B—Chetek sandy loam, 0 to 6 percent slopes

Map Unit Setting

National map unit symbol: 1t987

Elevation: 800 to 1,950 feet

Mean annual precipitation: 27 to 33 inches

Mean annual air temperature: 39 to 46 degrees F

Frost-free period: 135 to 180 days

Farmland classification: Farmland of statewide importance

Map Unit Composition

Chetek and similar soils: 90 percent

Minor components: 10 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Chetek

Setting

Landform: Outwash plains

Landform position (two-dimensional): Backslope

Down-slope shape: Linear

Across-slope shape: Linear

Parent material: Outwash

Typical profile

Ap - 0 to 8 inches: sandy loam

E - 8 to 14 inches: loam

Bt - 14 to 19 inches: gravelly sandy loam

2BC,2C - 19 to 60 inches: gravelly coarse sand

Properties and qualities

Slope: 0 to 6 percent

Depth to restrictive feature: More than 80 inches

Natural drainage class: Somewhat excessively drained

Capacity of the most limiting layer to transmit water (Ksat):

Moderately high to high (0.57 to 5.95 in/hr)

Depth to water table: More than 80 inches

Frequency of flooding: None

Frequency of ponding: None

Available water storage in profile: Low (about 3.7 inches)

Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 3e

Hydrologic Soil Group: A

Forage suitability group: Sandy (G090XN022MN)

Hydric soil rating: No

Minor Components

Kingsley

Percent of map unit: 5 percent

Hydric soil rating: No

Poskin

Percent of map unit: 5 percent

Hydric soil rating: No

Data Source Information

Soil Survey Area: Ramsey County, Minnesota

Survey Area Data: Version 15, Jun 5, 2020

Ramsey County, Minnesota

155C—Chetek sandy loam, 6 to 12 percent slopes

Map Unit Setting

National map unit symbol: 1t988

Elevation: 800 to 1,950 feet

Mean annual precipitation: 27 to 33 inches

Mean annual air temperature: 39 to 46 degrees F

Frost-free period: 135 to 180 days

Farmland classification: Not prime farmland

Map Unit Composition

Chetek and similar soils: 90 percent

Minor components: 10 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Chetek

Setting

Landform: Pitted outwash plains

Landform position (two-dimensional): Shoulder

Down-slope shape: Convex

Across-slope shape: Convex

Parent material: Outwash

Typical profile

Ap - 0 to 8 inches: sandy loam

E - 8 to 14 inches: loam

Bt - 14 to 19 inches: gravelly sandy loam

2BC,2C - 19 to 60 inches: gravelly coarse sand

Properties and qualities

Slope: 6 to 12 percent

Depth to restrictive feature: More than 80 inches

Natural drainage class: Somewhat excessively drained

Capacity of the most limiting layer to transmit water (Ksat):

Moderately high to high (0.57 to 5.95 in/hr)

Depth to water table: More than 80 inches

Frequency of flooding: None

Frequency of ponding: None

Available water storage in profile: Low (about 3.7 inches)

Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 4e

Hydrologic Soil Group: A

Forage suitability group: Sandy (G090XN022MN)

Hydric soil rating: No

Minor Components

Kingsley

Percent of map unit: 5 percent

Hydric soil rating: No

Poskin

Percent of map unit: 5 percent


Hydric soil rating: No

Data Source Information


Soil Survey Area: Ramsey County, Minnesota

Survey Area Data: Version 15, Jun 5, 2020


APPENDIX C – HydroCAD Reports





Existing SW



Existing N



Existing E



Routing Diagram for 22163 - Model

Prepared by Sambatek, Printed 7/24/2020

HydroCAD® 10.00-20 s/n 01876 © 2017 HydroCAD Software Solutions LLC

22163 - Model

Prepared by Sambatek

HydroCAD® 10.00-20 s/n 01876 © 2017 HydroCAD Software Solutions LLC

Printed 7/24/2020

Page 2

Area Listing (selected nodes)

Area (sq-ft)	CN	Description (subcatchment-numbers)
72,925	61	>75% Grass cover, Good, HSG B (E1, E2, E3)
245	98	Paved parking, HSG A (E1, E2)
73,170	61	TOTAL AREA

22163 - Model

Prepared by Sambatek

Printed 7/24/2020

HydroCAD® 10.00-20 s/n 01876 © 2017 HydroCAD Software Solutions LLC

Page 3

Soil Listing (selected nodes)

Area (sq-ft)	Soil Group	Subcatchment Numbers
245	HSG A	E1, E2
72,925	HSG B	E1, E2, E3
0	HSG C	
0	HSG D	
0	Other	
73,170		TOTAL AREA

22163 - Model*MSE 24-hr 3 2-Year Rainfall=2.81"*

Prepared by Sambatek

Printed 7/24/2020

HydroCAD® 10.00-20 s/n 01876 © 2017 HydroCAD Software Solutions LLC

Page 4

Time span=0.00-48.00 hrs, dt=0.05 hrs, 961 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

SubcatchmentE1: Existing SW

Runoff Area=53,791 sf 0.42% Impervious Runoff Depth=0.30"
Flow Length=295' Slope=0.0355 '/' Tc=19.7 min CN=61 Runoff=0.24 cfs 1,326 cf

SubcatchmentE2: Existing E

Runoff Area=14,092 sf 0.14% Impervious Runoff Depth=0.30"
Flow Length=172' Slope=0.0319 '/' Tc=13.4 min CN=61 Runoff=0.07 cfs 347 cf

SubcatchmentE3: Existing N

Runoff Area=5,287 sf 0.00% Impervious Runoff Depth=0.30"
Tc=10.0 min CN=61 Runoff=0.03 cfs 130 cf

Total Runoff Area = 73,170 sf Runoff Volume = 1,804 cf Average Runoff Depth = 0.30"
99.67% Pervious = 72,925 sf 0.33% Impervious = 245 sf

22163 - Model

Prepared by Sambatek

HydroCAD® 10.00-20 s/n 01876 © 2017 HydroCAD Software Solutions LLC

MSE 24-hr 3 2-Year Rainfall=2.81"

Printed 7/24/2020

Page 5

Summary for Subcatchment E1: Existing SW

Runoff = 0.24 cfs @ 12.40 hrs, Volume= 1,326 cf, Depth= 0.30"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-48.00 hrs, dt= 0.05 hrs
MSE 24-hr 3 2-Year Rainfall=2.81"

Area (sf)	CN	Description
225	98	Paved parking, HSG A
53,566	61	>75% Grass cover, Good, HSG B
53,791	61	Weighted Average
53,566		99.58% Pervious Area
225		0.42% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
19.7	295	0.0355	0.25		Sheet Flow, Grass: Short n= 0.150 P2= 2.81"

Subcatchment E1: Existing SW

Hydrograph



22163 - Model

Prepared by Sambatek

HydroCAD® 10.00-20 s/n 01876 © 2017 HydroCAD Software Solutions LLC

MSE 24-hr 3 2-Year Rainfall=2.81"

Printed 7/24/2020

Page 6

Summary for Subcatchment E2: Existing E

Runoff = 0.07 cfs @ 12.29 hrs, Volume= 347 cf, Depth= 0.30"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-48.00 hrs, dt= 0.05 hrs
MSE 24-hr 3 2-Year Rainfall=2.81"

Area (sf)	CN	Description
20	98	Paved parking, HSG A
14,072	61	>75% Grass cover, Good, HSG B
14,092	61	Weighted Average
14,072		99.86% Pervious Area
20		0.14% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
13.4	172	0.0319	0.21		Sheet Flow, Grass: Short n= 0.150 P2= 2.81"

Subcatchment E2: Existing E

Hydrograph



22163 - Model

Prepared by Sambatek

HydroCAD® 10.00-20 s/n 01876 © 2017 HydroCAD Software Solutions LLC

MSE 24-hr 3 2-Year Rainfall=2.81"

Printed 7/24/2020

Page 7

Summary for Subcatchment E3: Existing N

Runoff = 0.03 cfs @ 12.23 hrs, Volume= 130 cf, Depth= 0.30"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-48.00 hrs, dt= 0.05 hrs
MSE 24-hr 3 2-Year Rainfall=2.81"

Area (sf)	CN	Description
5,287	61	>75% Grass cover, Good, HSG B
5,287		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
10.0					Direct Entry,

Subcatchment E3: Existing N

Hydrograph



22163 - Model*MSE 24-hr 3 10-Year Rainfall=4.19"*

Prepared by Sambatek

Printed 7/24/2020

HydroCAD® 10.00-20 s/n 01876 © 2017 HydroCAD Software Solutions LLC

Page 8

Time span=0.00-48.00 hrs, dt=0.05 hrs, 961 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

SubcatchmentE1: Existing SW

Runoff Area=53,791 sf 0.42% Impervious Runoff Depth=0.91"
Flow Length=295' Slope=0.0355 '/' Tc=19.7 min CN=61 Runoff=1.09 cfs 4,083 cf

SubcatchmentE2: Existing E

Runoff Area=14,092 sf 0.14% Impervious Runoff Depth=0.91"
Flow Length=172' Slope=0.0319 '/' Tc=13.4 min CN=61 Runoff=0.35 cfs 1,070 cf

SubcatchmentE3: Existing N

Runoff Area=5,287 sf 0.00% Impervious Runoff Depth=0.91"
Tc=10.0 min CN=61 Runoff=0.15 cfs 401 cf

Total Runoff Area = 73,170 sf Runoff Volume = 5,554 cf Average Runoff Depth = 0.91"
99.67% Pervious = 72,925 sf 0.33% Impervious = 245 sf

22163 - Model

Prepared by Sambatek

HydroCAD® 10.00-20 s/n 01876 © 2017 HydroCAD Software Solutions LLC

MSE 24-hr 3 10-Year Rainfall=4.19"

Printed 7/24/2020

Page 9

Summary for Subcatchment E1: Existing SW

Runoff = 1.09 cfs @ 12.33 hrs, Volume= 4,083 cf, Depth= 0.91"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-48.00 hrs, dt= 0.05 hrs
MSE 24-hr 3 10-Year Rainfall=4.19"

Area (sf)	CN	Description
225	98	Paved parking, HSG A
53,566	61	>75% Grass cover, Good, HSG B
53,791	61	Weighted Average
53,566		99.58% Pervious Area
225		0.42% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
19.7	295	0.0355	0.25		Sheet Flow, Grass: Short n= 0.150 P2= 2.81"

Subcatchment E1: Existing SW

Hydrograph



22163 - Model

Prepared by Sambatek

HydroCAD® 10.00-20 s/n 01876 © 2017 HydroCAD Software Solutions LLC

MSE 24-hr 3 10-Year Rainfall=4.19"

Printed 7/24/2020

Page 10

Summary for Subcatchment E2: Existing E

Runoff = 0.35 cfs @ 12.24 hrs, Volume= 1,070 cf, Depth= 0.91"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-48.00 hrs, dt= 0.05 hrs
MSE 24-hr 3 10-Year Rainfall=4.19"

Area (sf)	CN	Description
20	98	Paved parking, HSG A
14,072	61	>75% Grass cover, Good, HSG B
14,092	61	Weighted Average
14,072		99.86% Pervious Area
20		0.14% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
13.4	172	0.0319	0.21		Sheet Flow, Grass: Short n= 0.150 P2= 2.81"

Subcatchment E2: Existing E

Hydrograph



22163 - Model

Prepared by Sambatek

HydroCAD® 10.00-20 s/n 01876 © 2017 HydroCAD Software Solutions LLC

MSE 24-hr 3 10-Year Rainfall=4.19"

Printed 7/24/2020

Page 11

Summary for Subcatchment E3: Existing N

Runoff = 0.15 cfs @ 12.20 hrs, Volume= 401 cf, Depth= 0.91"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-48.00 hrs, dt= 0.05 hrs
MSE 24-hr 3 10-Year Rainfall=4.19"

Area (sf)	CN	Description
5,287	61	>75% Grass cover, Good, HSG B
5,287		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
10.0					Direct Entry,

Subcatchment E3: Existing N

Hydrograph



22163 - Model*MSE 24-hr 3 100-Year Rainfall=7.36"*

Prepared by Sambatek

Printed 7/24/2020

HydroCAD® 10.00-20 s/n 01876 © 2017 HydroCAD Software Solutions LLC

Page 12

Time span=0.00-48.00 hrs, dt=0.05 hrs, 961 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

SubcatchmentE1: Existing SW

Runoff Area=53,791 sf 0.42% Impervious Runoff Depth=2.96"
Flow Length=295' Slope=0.0355 '/' Tc=19.7 min CN=61 Runoff=4.05 cfs 13,289 cf

SubcatchmentE2: Existing E

Runoff Area=14,092 sf 0.14% Impervious Runoff Depth=2.96"
Flow Length=172' Slope=0.0319 '/' Tc=13.4 min CN=61 Runoff=1.29 cfs 3,481 cf

SubcatchmentE3: Existing N

Runoff Area=5,287 sf 0.00% Impervious Runoff Depth=2.96"
Tc=10.0 min CN=61 Runoff=0.54 cfs 1,306 cf

Total Runoff Area = 73,170 sf Runoff Volume = 18,076 cf Average Runoff Depth = 2.96"
99.67% Pervious = 72,925 sf 0.33% Impervious = 245 sf

22163 - Model

Prepared by Sambatek

HydroCAD® 10.00-20 s/n 01876 © 2017 HydroCAD Software Solutions LLC

MSE 24-hr 3 100-Year Rainfall=7.36"

Printed 7/24/2020

Page 13

Summary for Subcatchment E1: Existing SW

Runoff = 4.05 cfs @ 12.31 hrs, Volume= 13,289 cf, Depth= 2.96"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-48.00 hrs, dt= 0.05 hrs
MSE 24-hr 3 100-Year Rainfall=7.36"

Area (sf)	CN	Description
225	98	Paved parking, HSG A
53,566	61	>75% Grass cover, Good, HSG B
53,791	61	Weighted Average
53,566		99.58% Pervious Area
225		0.42% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
19.7	295	0.0355	0.25		Sheet Flow, Grass: Short n= 0.150 P2= 2.81"

Subcatchment E1: Existing SW

Hydrograph



22163 - Model

Prepared by Sambatek

HydroCAD® 10.00-20 s/n 01876 © 2017 HydroCAD Software Solutions LLC

MSE 24-hr 3 100-Year Rainfall=7.36"

Printed 7/24/2020

Page 14

Summary for Subcatchment E2: Existing E

Runoff = 1.29 cfs @ 12.22 hrs, Volume= 3,481 cf, Depth= 2.96"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-48.00 hrs, dt= 0.05 hrs
MSE 24-hr 3 100-Year Rainfall=7.36"

Area (sf)	CN	Description
20	98	Paved parking, HSG A
14,072	61	>75% Grass cover, Good, HSG B
14,092	61	Weighted Average
14,072		99.86% Pervious Area
20		0.14% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
13.4	172	0.0319	0.21		Sheet Flow, Grass: Short n= 0.150 P2= 2.81"

Subcatchment E2: Existing E

Hydrograph



22163 - Model

Prepared by Sambatek

HydroCAD® 10.00-20 s/n 01876 © 2017 HydroCAD Software Solutions LLC

MSE 24-hr 3 100-Year Rainfall=7.36"

Printed 7/24/2020

Page 15

Summary for Subcatchment E3: Existing N

Runoff = 0.54 cfs @ 12.18 hrs, Volume= 1,306 cf, Depth= 2.96"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-48.00 hrs, dt= 0.05 hrs
MSE 24-hr 3 100-Year Rainfall=7.36"


Area (sf)	CN	Description
5,287	61	>75% Grass cover, Good, HSG B
5,287		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
10.0					Direct Entry,



Subcatchment E3: Existing N

Hydrograph





Proposed



22163 - Model

Prepared by Sambatek

Printed 7/24/2020

HydroCAD® 10.00-20 s/n 01876 © 2017 HydroCAD Software Solutions LLC

Page 2

Area Listing (selected nodes)

Area (sq-ft)	CN	Description (subcatchment-numbers)
12,324	61	>75% Grass cover, Good, HSG B (P1, P2, P3, P4, P5, P7, P8)
60,847	98	Paved parking, HSG B (P1, P2, P3, P4, P5, P6, P7)
73,171	92	TOTAL AREA

22163 - Model

Prepared by Sambatek

Printed 7/24/2020

HydroCAD® 10.00-20 s/n 01876 © 2017 HydroCAD Software Solutions LLC

Page 3

Soil Listing (selected nodes)

Area (sq-ft)	Soil Group	Subcatchment Numbers
0	HSG A	
73,171	HSG B	P1, P2, P3, P4, P5, P6, P7, P8
0	HSG C	
0	HSG D	
0	Other	
73,171		TOTAL AREA

22163 - Model

Prepared by Sambatek

HydroCAD® 10.00-20 s/n 01876 © 2017 HydroCAD Software Solutions LLC

MSE 24-hr 3 2-Year Rainfall=2.81"

Printed 7/24/2020

Page 4

Time span=0.00-48.00 hrs, dt=0.05 hrs, 961 points
 Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
 Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

SubcatchmentP1: Proposed NW Runoff Area=10,395 sf 83.88% Impervious Runoff Depth=1.98"
 Tc=7.0 min CN=92 Runoff=0.79 cfs 1,717 cf

SubcatchmentP2: Proposed NE Runoff Area=12,683 sf 83.43% Impervious Runoff Depth=1.98"
 Tc=7.0 min CN=92 Runoff=0.97 cfs 2,095 cf

SubcatchmentP3: Proposed E Runoff Area=6,835 sf 89.69% Impervious Runoff Depth=2.17"
 Tc=7.0 min CN=94 Runoff=0.56 cfs 1,234 cf

SubcatchmentP4: Proposed SE Runoff Area=13,536 sf 82.93% Impervious Runoff Depth=1.98"
 Tc=7.0 min CN=92 Runoff=1.03 cfs 2,236 cf

SubcatchmentP5: Proposed SW Runoff Area=9,341 sf 96.58% Impervious Runoff Depth=2.47"
 Tc=7.0 min CN=97 Runoff=0.82 cfs 1,923 cf

SubcatchmentP6: Proposed Building Runoff Area=12,654 sf 100.00% Impervious Runoff Depth=2.58"
 Tc=10.0 min CN=98 Runoff=1.01 cfs 2,720 cf

SubcatchmentP7: Off-Site SW Runoff Area=6,455 sf 38.96% Impervious Runoff Depth=0.84"
 Tc=7.0 min CN=75 Runoff=0.21 cfs 451 cf

SubcatchmentP8: Off-Site E Runoff Area=1,272 sf 0.00% Impervious Runoff Depth=0.30"
 Tc=7.0 min CN=61 Runoff=0.01 cfs 31 cf

Pond 1P: Subsurface System Peak Elev=921.25' Storage=7,793 cf Inflow=5.14 cfs 11,925 cf
 Discarded=0.07 cfs 10,416 cf Primary=0.20 cfs 1,493 cf Secondary=0.00 cfs 0 cf Outflow=0.28 cfs 11,909 cf

Link 1L: SW Total Inflow=0.22 cfs 1,944 cf
 Primary=0.22 cfs 1,944 cf

Link 3L: E Total Inflow=0.01 cfs 31 cf
 Primary=0.01 cfs 31 cf

Total Runoff Area = 73,171 sf Runoff Volume = 12,407 cf Average Runoff Depth = 2.03"
16.84% Pervious = 12,324 sf 83.16% Impervious = 60,847 sf

22163 - Model

Prepared by Sambatek

HydroCAD® 10.00-20 s/n 01876 © 2017 HydroCAD Software Solutions LLC

MSE 24-hr 3 2-Year Rainfall=2.81"

Printed 7/24/2020

Page 5

Summary for Subcatchment P1: Proposed NW

Runoff = 0.79 cfs @ 12.14 hrs, Volume= 1,717 cf, Depth= 1.98"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-48.00 hrs, dt= 0.05 hrs
MSE 24-hr 3 2-Year Rainfall=2.81"

Area (sf)	CN	Description
1,676	61	>75% Grass cover, Good, HSG B
8,719	98	Paved parking, HSG B
10,395	92	Weighted Average
1,676		16.12% Pervious Area
8,719		83.88% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
7.0					Direct Entry,

Subcatchment P1: Proposed NW

Hydrograph



22163 - Model

Prepared by Sambatek

HydroCAD® 10.00-20 s/n 01876 © 2017 HydroCAD Software Solutions LLC

MSE 24-hr 3 2-Year Rainfall=2.81"

Printed 7/24/2020

Page 6

Summary for Subcatchment P2: Proposed NE

Runoff = 0.97 cfs @ 12.14 hrs, Volume= 2,095 cf, Depth= 1.98"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-48.00 hrs, dt= 0.05 hrs
MSE 24-hr 3 2-Year Rainfall=2.81"

Area (sf)	CN	Description
2,102	61	>75% Grass cover, Good, HSG B
10,581	98	Paved parking, HSG B
12,683	92	Weighted Average
2,102		16.57% Pervious Area
10,581		83.43% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
7.0					Direct Entry,

Subcatchment P2: Proposed NE

Hydrograph



22163 - Model

Prepared by Sambatek

HydroCAD® 10.00-20 s/n 01876 © 2017 HydroCAD Software Solutions LLC

MSE 24-hr 3 2-Year Rainfall=2.81"

Printed 7/24/2020

Page 7

Summary for Subcatchment P3: Proposed E

Runoff = 0.56 cfs @ 12.14 hrs, Volume= 1,234 cf, Depth= 2.17"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-48.00 hrs, dt= 0.05 hrs
MSE 24-hr 3 2-Year Rainfall=2.81"

Area (sf)	CN	Description
705	61	>75% Grass cover, Good, HSG B
6,130	98	Paved parking, HSG B
6,835	94	Weighted Average
705		10.31% Pervious Area
6,130		89.69% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
7.0					Direct Entry,

Subcatchment P3: Proposed E

Hydrograph



22163 - Model

Prepared by Sambatek

HydroCAD® 10.00-20 s/n 01876 © 2017 HydroCAD Software Solutions LLC

MSE 24-hr 3 2-Year Rainfall=2.81"

Printed 7/24/2020

Page 8

Summary for Subcatchment P4: Proposed SE

Runoff = 1.03 cfs @ 12.14 hrs, Volume= 2,236 cf, Depth= 1.98"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-48.00 hrs, dt= 0.05 hrs
MSE 24-hr 3 2-Year Rainfall=2.81"

Area (sf)	CN	Description
2,310	61	>75% Grass cover, Good, HSG B
11,226	98	Paved parking, HSG B
13,536	92	Weighted Average
2,310		17.07% Pervious Area
11,226		82.93% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
7.0					Direct Entry,

Subcatchment P4: Proposed SE

Hydrograph



22163 - Model

Prepared by Sambatek

HydroCAD® 10.00-20 s/n 01876 © 2017 HydroCAD Software Solutions LLC

MSE 24-hr 3 2-Year Rainfall=2.81"

Printed 7/24/2020

Page 9

Summary for Subcatchment P5: Proposed SW

Runoff = 0.82 cfs @ 12.14 hrs, Volume= 1,923 cf, Depth= 2.47"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-48.00 hrs, dt= 0.05 hrs
MSE 24-hr 3 2-Year Rainfall=2.81"

Area (sf)	CN	Description
319	61	>75% Grass cover, Good, HSG B
9,022	98	Paved parking, HSG B
9,341	97	Weighted Average
319		3.42% Pervious Area
9,022		96.58% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
7.0					Direct Entry,

Subcatchment P5: Proposed SW

Hydrograph



22163 - Model

Prepared by Sambatek

HydroCAD® 10.00-20 s/n 01876 © 2017 HydroCAD Software Solutions LLC

MSE 24-hr 3 2-Year Rainfall=2.81"

Printed 7/24/2020

Page 10

Summary for Subcatchment P6: Proposed Building

Runoff = 1.01 cfs @ 12.17 hrs, Volume= 2,720 cf, Depth= 2.58"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-48.00 hrs, dt= 0.05 hrs
MSE 24-hr 3 2-Year Rainfall=2.81"

Area (sf)	CN	Description
12,654	98	Paved parking, HSG B
12,654		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
10.0					Direct Entry,

Subcatchment P6: Proposed Building

Hydrograph



22163 - Model

Prepared by Sambatek

HydroCAD® 10.00-20 s/n 01876 © 2017 HydroCAD Software Solutions LLC

MSE 24-hr 3 2-Year Rainfall=2.81"

Printed 7/24/2020

Page 11

Summary for Subcatchment P7: Off-Site SW

Runoff = 0.21 cfs @ 12.15 hrs, Volume= 451 cf, Depth= 0.84"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-48.00 hrs, dt= 0.05 hrs
MSE 24-hr 3 2-Year Rainfall=2.81"

Area (sf)	CN	Description
3,940	61	>75% Grass cover, Good, HSG B
2,515	98	Paved parking, HSG B
6,455	75	Weighted Average
3,940		61.04% Pervious Area
2,515		38.96% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
7.0					Direct Entry,

Subcatchment P7: Off-Site SW

Hydrograph



22163 - Model

Prepared by Sambatek

HydroCAD® 10.00-20 s/n 01876 © 2017 HydroCAD Software Solutions LLC

MSE 24-hr 3 2-Year Rainfall=2.81"

Printed 7/24/2020

Page 12

Summary for Subcatchment P8: Off-Site E

Runoff = 0.01 cfs @ 12.18 hrs, Volume= 31 cf, Depth= 0.30"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-48.00 hrs, dt= 0.05 hrs
MSE 24-hr 3 2-Year Rainfall=2.81"

Area (sf)	CN	Description
1,272	61	>75% Grass cover, Good, HSG B
1,272		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
7.0					Direct Entry,

Subcatchment P8: Off-Site E

Hydrograph



22163 - Model

Prepared by Sambatek

HydroCAD® 10.00-20 s/n 01876 © 2017 HydroCAD Software Solutions LLC

MSE 24-hr 3 2-Year Rainfall=2.81"

Printed 7/24/2020

Page 13

Summary for Pond 1P: Subsurface System

Inflow Area = 65,444 sf, 89.13% Impervious, Inflow Depth = 2.19" for 2-Year event
 Inflow = 5.14 cfs @ 12.14 hrs, Volume= 11,925 cf
 Outflow = 0.28 cfs @ 13.42 hrs, Volume= 11,909 cf, Atten= 95%, Lag= 76.8 min
 Discarded = 0.07 cfs @ 10.40 hrs, Volume= 10,416 cf
 Primary = 0.20 cfs @ 13.42 hrs, Volume= 1,493 cf
 Secondary = 0.00 cfs @ 0.00 hrs, Volume= 0 cf

Routing by Stor-Ind method, Time Span= 0.00-48.00 hrs, dt= 0.05 hrs
 Peak Elev= 921.25' @ 13.42 hrs Surf.Area= 4,032 sf Storage= 7,793 cf

Plug-Flow detention time= 800.5 min calculated for 11,896 cf (100% of inflow)
 Center-of-Mass det. time= 800.3 min (1,575.8 - 775.5)

Volume	Invert	Avail.Storage	Storage Description
#1	925.25'	2,074 cf	Low Inlet Overflow (Prismatic) Listed below (Recalc)
#2A	918.50'	5,655 cf	29.92'W x 134.76'L x 5.50'H Field A 22,174 cf Overall - 8,036 cf Embedded = 14,138 cf x 40.0% Voids
#3A	919.25'	8,036 cf	ADS_StormTech MC-3500 d +Capx 72 Inside #2 Effective Size= 70.4"W x 45.0"H => 15.33 sf x 7.17'L = 110.0 cf Overall Size= 77.0"W x 45.0"H x 7.50'L with 0.33' Overlap 4 Rows of 18 Chambers Cap Storage= +14.9 cf x 2 x 4 rows = 119.2 cf
		15,765 cf	Total Available Storage

Storage Group A created with Chamber Wizard

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
925.25	13	0	0
926.00	650	249	249
927.00	3,000	1,825	2,074

Device	Routing	Invert	Outlet Devices
#1	Primary	921.00'	15.0" Round Culvert L= 10.0' RCP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 921.00' / 920.96' S= 0.0040 ' S= 0.0040 ' Cc= 0.900 n= 0.013 Concrete pipe, bends & connections, Flow Area= 1.23 sf
#2	Discarded	918.50'	0.800 in/hr Exfiltration over Surface area
#3	Secondary	925.50'	10.0' long x 4.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.38 2.54 2.69 2.68 2.67 2.67 2.65 2.66 2.66 2.68 2.72 2.73 2.76 2.79 2.88 3.07 3.32

22163 - Model

Prepared by Sambatek

HydroCAD® 10.00-20 s/n 01876 © 2017 HydroCAD Software Solutions LLC

MSE 24-hr 3 2-Year Rainfall=2.81"

Printed 7/24/2020

Page 14

Discarded OutFlow Max=0.07 cfs @ 10.40 hrs HW=918.59' (Free Discharge)

↑**2=Exfiltration** (Exfiltration Controls 0.07 cfs)

Primary OutFlow Max=0.20 cfs @ 13.42 hrs HW=921.25' (Free Discharge)

↑**1=Culvert** (Barrel Controls 0.20 cfs @ 1.69 fps)

Secondary OutFlow Max=0.00 cfs @ 0.00 hrs HW=918.50' (Free Discharge)

↑**3=Broad-Crested Rectangular Weir** (Controls 0.00 cfs)

22163 - Model

Prepared by Sambatek

HydroCAD® 10.00-20 s/n 01876 © 2017 HydroCAD Software Solutions LLC

MSE 24-hr 3 2-Year Rainfall=2.81"

Printed 7/24/2020

Page 15

Pond 1P: Subsurface System - Chamber Wizard Field A

Chamber Model = ADS_StormTechMC-3500 d +Cap (ADS StormTech®MC-3500 d rev 03/14 with Cap volume)

Effective Size= 70.4"W x 45.0"H => 15.33 sf x 7.17'L = 110.0 cf

Overall Size= 77.0"W x 45.0"H x 7.50'L with 0.33' Overlap

Cap Storage= +14.9 cf x 2 x 4 rows = 119.2 cf

77.0" Wide + 9.0" Spacing = 86.0" C-C Row Spacing

18 Chambers/Row x 7.17' Long +1.85' Cap Length x 2 = 132.76' Row Length +12.0" End Stone x 2 = 134.76' Base Length

4 Rows x 77.0" Wide + 9.0" Spacing x 3 + 12.0" Side Stone x 2 = 29.92' Base Width

9.0" Base + 45.0" Chamber Height + 12.0" Cover = 5.50' Field Height

72 Chambers x 110.0 cf + 14.9 cf Cap Volume x 2 x 4 Rows = 8,035.7 cf Chamber Storage

22,173.6 cf Field - 8,035.7 cf Chambers = 14,137.9 cf Stone x 40.0% Voids = 5,655.2 cf Stone Storage

Chamber Storage + Stone Storage = 13,690.9 cf = 0.314 af


Overall Storage Efficiency = 61.7%


Overall System Size = 134.76' x 29.92' x 5.50'

72 Chambers

821.2 cy Field

523.6 cy Stone



Pond 1P: Subsurface System

22163 - Model

Prepared by Sambatek

HydroCAD® 10.00-20 s/n 01876 © 2017 HydroCAD Software Solutions LLC

MSE 24-hr 3 2-Year Rainfall=2.81"

Printed 7/24/2020

Page 17


Stage-Area-Storage for Pond 1P: Subsurface System

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
918.50	4,032	0	923.70	4,032	13,207
918.60	4,032	161	923.80	4,032	13,368
918.70	4,032	323	923.90	4,032	13,530
918.80	4,032	484	924.00	4,032	13,691
918.90	4,032	645	924.10	4,032	13,691
919.00	4,032	806	924.20	4,032	13,691
919.10	4,032	968	924.30	4,032	13,691
919.20	4,032	1,129	924.40	4,032	13,691
919.30	4,032	1,382	924.50	4,032	13,691
919.40	4,032	1,727	924.60	4,032	13,691
919.50	4,032	2,070	924.70	4,032	13,691
919.60	4,032	2,412	924.80	4,032	13,691
919.70	4,032	2,753	924.90	4,032	13,691
919.80	4,032	3,092	925.00	4,032	13,691
919.90	4,032	3,430	925.10	4,032	13,691
920.00	4,032	3,766	925.20	4,032	13,691
920.10	4,032	4,100	925.30	4,087	13,693
920.20	4,032	4,433	925.40	4,172	13,702
920.30	4,032	4,763	925.50	4,257	13,721
920.40	4,032	5,092	925.60	4,342	13,747
920.50	4,032	5,418	925.70	4,427	13,783
920.60	4,032	5,742	925.80	4,512	13,827
920.70	4,032	6,063	925.90	4,597	13,879
920.80	4,032	6,382	926.00	4,682	13,940
920.90	4,032	6,698	926.10	4,917	14,016
921.00	4,032	7,010	926.20	5,152	14,117
921.10	4,032	7,320	926.30	5,387	14,240
921.20	4,032	7,626	926.40	5,622	14,388
921.30	4,032	7,929	926.50	5,857	14,558
921.40	4,032	8,228	926.60	6,092	14,753
921.50	4,032	8,523	926.70	6,327	14,970
921.60	4,032	8,813	926.80	6,562	15,212
921.70	4,032	9,098	926.90	6,797	15,476
921.80	4,032	9,379	927.00	7,032	15,765
921.90	4,032	9,654			
922.00	4,032	9,923			
922.10	4,032	10,186			
922.20	4,032	10,441			
922.30	4,032	10,689			
922.40	4,032	10,927			
922.50	4,032	11,154			
922.60	4,032	11,366			
922.70	4,032	11,560			
922.80	4,032	11,740			
922.90	4,032	11,913			
923.00	4,032	12,078			
923.10	4,032	12,240			
923.20	4,032	12,401			
923.30	4,032	12,562			
923.40	4,032	12,723			
923.50	4,032	12,885			
923.60	4,032	13,046			

Summary for Link 1L: SW Total

Inflow Area = 71,899 sf, 84.63% Impervious, Inflow Depth = 0.32" for 2-Year event
Inflow = 0.22 cfs @ 13.40 hrs, Volume= 1,944 cf
Primary = 0.22 cfs @ 13.40 hrs, Volume= 1,944 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-48.00 hrs, dt= 0.05 hrs

Link 1L: SW Total**Hydrograph**


Summary for Link 3L: E Total

Inflow Area = 1,272 sf, 0.00% Impervious, Inflow Depth = 0.30" for 2-Year event
Inflow = 0.01 cfs @ 12.18 hrs, Volume= 31 cf
Primary = 0.01 cfs @ 12.18 hrs, Volume= 31 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-48.00 hrs, dt= 0.05 hrs

Link 3L: E Total

Hydrograph



22163 - Model

Prepared by Sambatek

HydroCAD® 10.00-20 s/n 01876 © 2017 HydroCAD Software Solutions LLC

MSE 24-hr 3 10-Year Rainfall=4.19"

Printed 7/24/2020

Page 20

Time span=0.00-48.00 hrs, dt=0.05 hrs, 961 points
 Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
 Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

SubcatchmentP1: Proposed NW Runoff Area=10,395 sf 83.88% Impervious Runoff Depth=3.30"
 Tc=7.0 min CN=92 Runoff=1.28 cfs 2,860 cf

SubcatchmentP2: Proposed NE Runoff Area=12,683 sf 83.43% Impervious Runoff Depth=3.30"
 Tc=7.0 min CN=92 Runoff=1.56 cfs 3,489 cf

SubcatchmentP3: Proposed E Runoff Area=6,835 sf 89.69% Impervious Runoff Depth=3.51"
 Tc=7.0 min CN=94 Runoff=0.87 cfs 2,000 cf

SubcatchmentP4: Proposed SE Runoff Area=13,536 sf 82.93% Impervious Runoff Depth=3.30"
 Tc=7.0 min CN=92 Runoff=1.67 cfs 3,724 cf

SubcatchmentP5: Proposed SW Runoff Area=9,341 sf 96.58% Impervious Runoff Depth=3.84"
 Tc=7.0 min CN=97 Runoff=1.25 cfs 2,989 cf

SubcatchmentP6: Proposed Building Runoff Area=12,654 sf 100.00% Impervious Runoff Depth=3.95"
 Tc=10.0 min CN=98 Runoff=1.51 cfs 4,170 cf

SubcatchmentP7: Off-Site SW Runoff Area=6,455 sf 38.96% Impervious Runoff Depth=1.81"
 Tc=7.0 min CN=75 Runoff=0.47 cfs 974 cf

SubcatchmentP8: Off-Site E Runoff Area=1,272 sf 0.00% Impervious Runoff Depth=0.91"
 Tc=7.0 min CN=61 Runoff=0.04 cfs 97 cf

Pond 1P: Subsurface System Peak Elev=921.93' Storage=9,739 cf Inflow=8.09 cfs 19,232 cf
 Discarded=0.07 cfs 10,999 cf Primary=2.26 cfs 7,988 cf Secondary=0.00 cfs 0 cf Outflow=2.33 cfs 18,987 cf

Link 1L: SW Total Inflow=2.40 cfs 8,962 cf
 Primary=2.40 cfs 8,962 cf

Link 3L: E Total Inflow=0.04 cfs 97 cf
 Primary=0.04 cfs 97 cf

Total Runoff Area = 73,171 sf Runoff Volume = 20,303 cf Average Runoff Depth = 3.33"
16.84% Pervious = 12,324 sf 83.16% Impervious = 60,847 sf

22163 - Model

Prepared by Sambatek

HydroCAD® 10.00-20 s/n 01876 © 2017 HydroCAD Software Solutions LLC

MSE 24-hr 3 10-Year Rainfall=4.19"

Printed 7/24/2020

Page 21

Summary for Subcatchment P1: Proposed NW

Runoff = 1.28 cfs @ 12.14 hrs, Volume= 2,860 cf, Depth= 3.30"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-48.00 hrs, dt= 0.05 hrs
MSE 24-hr 3 10-Year Rainfall=4.19"

Area (sf)	CN	Description
1,676	61	>75% Grass cover, Good, HSG B
8,719	98	Paved parking, HSG B
10,395	92	Weighted Average
1,676		16.12% Pervious Area
8,719		83.88% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
7.0					Direct Entry,

Subcatchment P1: Proposed NW

Hydrograph



22163 - Model

Prepared by Sambatek

HydroCAD® 10.00-20 s/n 01876 © 2017 HydroCAD Software Solutions LLC

MSE 24-hr 3 10-Year Rainfall=4.19"

Printed 7/24/2020

Page 22


Summary for Subcatchment P2: Proposed NE

Runoff = 1.56 cfs @ 12.14 hrs, Volume= 3,489 cf, Depth= 3.30"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-48.00 hrs, dt= 0.05 hrs
MSE 24-hr 3 10-Year Rainfall=4.19"

Area (sf)	CN	Description
2,102	61	>75% Grass cover, Good, HSG B
10,581	98	Paved parking, HSG B
12,683	92	Weighted Average
2,102		16.57% Pervious Area
10,581		83.43% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
7.0					Direct Entry,

Subcatchment P2: Proposed NE

22163 - Model

Prepared by Sambatek

HydroCAD® 10.00-20 s/n 01876 © 2017 HydroCAD Software Solutions LLC

MSE 24-hr 3 10-Year Rainfall=4.19"

Printed 7/24/2020

Page 23

Summary for Subcatchment P3: Proposed E

Runoff = 0.87 cfs @ 12.14 hrs, Volume= 2,000 cf, Depth= 3.51"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-48.00 hrs, dt= 0.05 hrs
MSE 24-hr 3 10-Year Rainfall=4.19"

Area (sf)	CN	Description
705	61	>75% Grass cover, Good, HSG B
6,130	98	Paved parking, HSG B
6,835	94	Weighted Average
705		10.31% Pervious Area
6,130		89.69% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
7.0					Direct Entry,

Subcatchment P3: Proposed E

Hydrograph



22163 - Model

Prepared by Sambatek

HydroCAD® 10.00-20 s/n 01876 © 2017 HydroCAD Software Solutions LLC

MSE 24-hr 3 10-Year Rainfall=4.19"

Printed 7/24/2020

Page 24

Summary for Subcatchment P4: Proposed SE

Runoff = 1.67 cfs @ 12.14 hrs, Volume= 3,724 cf, Depth= 3.30"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-48.00 hrs, dt= 0.05 hrs
MSE 24-hr 3 10-Year Rainfall=4.19"

Area (sf)	CN	Description
2,310	61	>75% Grass cover, Good, HSG B
11,226	98	Paved parking, HSG B
13,536	92	Weighted Average
2,310		17.07% Pervious Area
11,226		82.93% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
7.0					Direct Entry,

Subcatchment P4: Proposed SE

Hydrograph



22163 - Model

Prepared by Sambatek

HydroCAD® 10.00-20 s/n 01876 © 2017 HydroCAD Software Solutions LLC

MSE 24-hr 3 10-Year Rainfall=4.19"

Printed 7/24/2020

Page 25

Summary for Subcatchment P5: Proposed SW

Runoff = 1.25 cfs @ 12.14 hrs, Volume= 2,989 cf, Depth= 3.84"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-48.00 hrs, dt= 0.05 hrs
MSE 24-hr 3 10-Year Rainfall=4.19"

Area (sf)	CN	Description
319	61	>75% Grass cover, Good, HSG B
9,022	98	Paved parking, HSG B
9,341	97	Weighted Average
319		3.42% Pervious Area
9,022		96.58% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
7.0					Direct Entry,

Subcatchment P5: Proposed SW

Hydrograph



22163 - Model

Prepared by Sambatek

HydroCAD® 10.00-20 s/n 01876 © 2017 HydroCAD Software Solutions LLC

MSE 24-hr 3 10-Year Rainfall=4.19"

Printed 7/24/2020

Page 26

Summary for Subcatchment P6: Proposed Building

Runoff = 1.51 cfs @ 12.17 hrs, Volume= 4,170 cf, Depth= 3.95"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-48.00 hrs, dt= 0.05 hrs
MSE 24-hr 3 10-Year Rainfall=4.19"

Area (sf)	CN	Description
12,654	98	Paved parking, HSG B
12,654		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
10.0					Direct Entry,

Subcatchment P6: Proposed Building

Hydrograph



22163 - Model

Prepared by Sambatek

HydroCAD® 10.00-20 s/n 01876 © 2017 HydroCAD Software Solutions LLC

MSE 24-hr 3 10-Year Rainfall=4.19"

Printed 7/24/2020

Page 27

Summary for Subcatchment P7: Off-Site SW

Runoff = 0.47 cfs @ 12.15 hrs, Volume= 974 cf, Depth= 1.81"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-48.00 hrs, dt= 0.05 hrs
MSE 24-hr 3 10-Year Rainfall=4.19"

Area (sf)	CN	Description
3,940	61	>75% Grass cover, Good, HSG B
2,515	98	Paved parking, HSG B
6,455	75	Weighted Average
3,940		61.04% Pervious Area
2,515		38.96% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
7.0					Direct Entry,

Subcatchment P7: Off-Site SW

Hydrograph



22163 - Model

Prepared by Sambatek

HydroCAD® 10.00-20 s/n 01876 © 2017 HydroCAD Software Solutions LLC

MSE 24-hr 3 10-Year Rainfall=4.19"

Printed 7/24/2020

Page 28

Summary for Subcatchment P8: Off-Site E

Runoff = 0.04 cfs @ 12.16 hrs, Volume= 97 cf, Depth= 0.91"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-48.00 hrs, dt= 0.05 hrs
MSE 24-hr 3 10-Year Rainfall=4.19"

Area (sf)	CN	Description
1,272	61	>75% Grass cover, Good, HSG B
1,272		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
7.0					Direct Entry,

Subcatchment P8: Off-Site E

Hydrograph



22163 - Model

Prepared by Sambatek

HydroCAD® 10.00-20 s/n 01876 © 2017 HydroCAD Software Solutions LLC

MSE 24-hr 3 10-Year Rainfall=4.19"

Printed 7/24/2020

Page 29

Summary for Pond 1P: Subsurface System

Inflow Area = 65,444 sf, 89.13% Impervious, Inflow Depth = 3.53" for 10-Year event
 Inflow = 8.09 cfs @ 12.14 hrs, Volume= 19,232 cf
 Outflow = 2.33 cfs @ 12.37 hrs, Volume= 18,987 cf, Atten= 71%, Lag= 13.4 min
 Discarded = 0.07 cfs @ 9.25 hrs, Volume= 10,999 cf
 Primary = 2.26 cfs @ 12.37 hrs, Volume= 7,988 cf
 Secondary = 0.00 cfs @ 0.00 hrs, Volume= 0 cf

Routing by Stor-Ind method, Time Span= 0.00-48.00 hrs, dt= 0.05 hrs
 Peak Elev= 921.93' @ 12.37 hrs Surf.Area= 4,032 sf Storage= 9,739 cf

Plug-Flow detention time= 535.0 min calculated for 18,967 cf (99% of inflow)
 Center-of-Mass det. time= 528.3 min (1,295.5 - 767.2)

Volume	Invert	Avail.Storage	Storage Description
#1	925.25'	2,074 cf	Low Inlet Overflow (Prismatic) Listed below (Recalc)
#2A	918.50'	5,655 cf	29.92'W x 134.76'L x 5.50'H Field A 22,174 cf Overall - 8,036 cf Embedded = 14,138 cf x 40.0% Voids
#3A	919.25'	8,036 cf	ADS_StormTech MC-3500 d +Cap x 72 Inside #2 Effective Size= 70.4"W x 45.0"H => 15.33 sf x 7.17'L = 110.0 cf Overall Size= 77.0"W x 45.0"H x 7.50'L with 0.33' Overlap 4 Rows of 18 Chambers Cap Storage= +14.9 cf x 2 x 4 rows = 119.2 cf
		15,765 cf	Total Available Storage

Storage Group A created with Chamber Wizard

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
925.25	13	0	0
926.00	650	249	249
927.00	3,000	1,825	2,074

Device	Routing	Invert	Outlet Devices
#1	Primary	921.00'	15.0" Round Culvert L= 10.0' RCP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 921.00' / 920.96' S= 0.0040 ' S= 0.0040 ' Cc= 0.900 n= 0.013 Concrete pipe, bends & connections, Flow Area= 1.23 sf
#2	Discarded	918.50'	0.800 in/hr Exfiltration over Surface area
#3	Secondary	925.50'	10.0' long x 4.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.38 2.54 2.69 2.68 2.67 2.67 2.65 2.66 2.66 2.68 2.72 2.73 2.76 2.79 2.88 3.07 3.32

22163 - Model

Prepared by Sambatek

HydroCAD® 10.00-20 s/n 01876 © 2017 HydroCAD Software Solutions LLC

MSE 24-hr 3 10-Year Rainfall=4.19"

Printed 7/24/2020

Page 30

Discarded OutFlow Max=0.07 cfs @ 9.25 hrs HW=918.59' (Free Discharge)

↑**2=Exfiltration** (Exfiltration Controls 0.07 cfs)

Primary OutFlow Max=2.24 cfs @ 12.37 hrs HW=921.93' (Free Discharge)

↑**1=Culvert** (Barrel Controls 2.24 cfs @ 3.19 fps)

Secondary OutFlow Max=0.00 cfs @ 0.00 hrs HW=918.50' (Free Discharge)

↑**3=Broad-Crested Rectangular Weir** (Controls 0.00 cfs)

22163 - Model

Prepared by Sambatek

HydroCAD® 10.00-20 s/n 01876 © 2017 HydroCAD Software Solutions LLC

MSE 24-hr 3 10-Year Rainfall=4.19"

Printed 7/24/2020

Page 31

Pond 1P: Subsurface System - Chamber Wizard Field A

Chamber Model = ADS_StormTechMC-3500 d +Cap (ADS StormTech®MC-3500 d rev 03/14 with Cap volume)

Effective Size= 70.4"W x 45.0"H => 15.33 sf x 7.17'L = 110.0 cf

Overall Size= 77.0"W x 45.0"H x 7.50'L with 0.33' Overlap

Cap Storage= +14.9 cf x 2 x 4 rows = 119.2 cf

77.0" Wide + 9.0" Spacing = 86.0" C-C Row Spacing

18 Chambers/Row x 7.17' Long +1.85' Cap Length x 2 = 132.76' Row Length +12.0" End Stone x 2 = 134.76' Base Length

4 Rows x 77.0" Wide + 9.0" Spacing x 3 + 12.0" Side Stone x 2 = 29.92' Base Width

9.0" Base + 45.0" Chamber Height + 12.0" Cover = 5.50' Field Height

72 Chambers x 110.0 cf + 14.9 cf Cap Volume x 2 x 4 Rows = 8,035.7 cf Chamber Storage

22,173.6 cf Field - 8,035.7 cf Chambers = 14,137.9 cf Stone x 40.0% Voids = 5,655.2 cf Stone Storage

Chamber Storage + Stone Storage = 13,690.9 cf = 0.314 af


Overall Storage Efficiency = 61.7%


Overall System Size = 134.76' x 29.92' x 5.50'

72 Chambers

821.2 cy Field

523.6 cy Stone



Pond 1P: Subsurface System

22163 - Model

Prepared by Sambatek

HydroCAD® 10.00-20 s/n 01876 © 2017 HydroCAD Software Solutions LLC

MSE 24-hr 3 10-Year Rainfall=4.19"

Printed 7/24/2020

Page 33

Stage-Area-Storage for Pond 1P: Subsurface System

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
918.50	4,032	0	923.70	4,032	13,207
918.60	4,032	161	923.80	4,032	13,368
918.70	4,032	323	923.90	4,032	13,530
918.80	4,032	484	924.00	4,032	13,691
918.90	4,032	645	924.10	4,032	13,691
919.00	4,032	806	924.20	4,032	13,691
919.10	4,032	968	924.30	4,032	13,691
919.20	4,032	1,129	924.40	4,032	13,691
919.30	4,032	1,382	924.50	4,032	13,691
919.40	4,032	1,727	924.60	4,032	13,691
919.50	4,032	2,070	924.70	4,032	13,691
919.60	4,032	2,412	924.80	4,032	13,691
919.70	4,032	2,753	924.90	4,032	13,691
919.80	4,032	3,092	925.00	4,032	13,691
919.90	4,032	3,430	925.10	4,032	13,691
920.00	4,032	3,766	925.20	4,032	13,691
920.10	4,032	4,100	925.30	4,087	13,693
920.20	4,032	4,433	925.40	4,172	13,702
920.30	4,032	4,763	925.50	4,257	13,721
920.40	4,032	5,092	925.60	4,342	13,747
920.50	4,032	5,418	925.70	4,427	13,783
920.60	4,032	5,742	925.80	4,512	13,827
920.70	4,032	6,063	925.90	4,597	13,879
920.80	4,032	6,382	926.00	4,682	13,940
920.90	4,032	6,698	926.10	4,917	14,016
921.00	4,032	7,010	926.20	5,152	14,117
921.10	4,032	7,320	926.30	5,387	14,240
921.20	4,032	7,626	926.40	5,622	14,388
921.30	4,032	7,929	926.50	5,857	14,558
921.40	4,032	8,228	926.60	6,092	14,753
921.50	4,032	8,523	926.70	6,327	14,970
921.60	4,032	8,813	926.80	6,562	15,212
921.70	4,032	9,098	926.90	6,797	15,476
921.80	4,032	9,379	927.00	7,032	15,765
921.90	4,032	9,654			
922.00	4,032	9,923			
922.10	4,032	10,186			
922.20	4,032	10,441			
922.30	4,032	10,689			
922.40	4,032	10,927			
922.50	4,032	11,154			
922.60	4,032	11,366			
922.70	4,032	11,560			
922.80	4,032	11,740			
922.90	4,032	11,913			
923.00	4,032	12,078			
923.10	4,032	12,240			
923.20	4,032	12,401			
923.30	4,032	12,562			
923.40	4,032	12,723			
923.50	4,032	12,885			
923.60	4,032	13,046			

22163 - Model

Prepared by Sambatek

HydroCAD® 10.00-20 s/n 01876 © 2017 HydroCAD Software Solutions LLC

MSE 24-hr 3 10-Year Rainfall=4.19"

Printed 7/24/2020

Page 34


Summary for Link 1L: SW Total

Inflow Area = 71,899 sf, 84.63% Impervious, Inflow Depth = 1.50" for 10-Year event
Inflow = 2.40 cfs @ 12.36 hrs, Volume= 8,962 cf
Primary = 2.40 cfs @ 12.36 hrs, Volume= 8,962 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-48.00 hrs, dt= 0.05 hrs

Link 1L: SW Total

Hydrograph



22163 - Model

Prepared by Sambatek

HydroCAD® 10.00-20 s/n 01876 © 2017 HydroCAD Software Solutions LLC

MSE 24-hr 3 10-Year Rainfall=4.19"

Printed 7/24/2020

Page 35


Summary for Link 3L: E Total

Inflow Area = 1,272 sf, 0.00% Impervious, Inflow Depth = 0.91" for 10-Year event
Inflow = 0.04 cfs @ 12.16 hrs, Volume= 97 cf
Primary = 0.04 cfs @ 12.16 hrs, Volume= 97 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-48.00 hrs, dt= 0.05 hrs

Link 3L: E Total

Hydrograph



22163 - Model*MSE 24-hr 3 100-Year Rainfall=7.36"*

Prepared by Sambatek

Printed 7/24/2020

HydroCAD® 10.00-20 s/n 01876 © 2017 HydroCAD Software Solutions LLC

Page 36

Time span=0.00-48.00 hrs, dt=0.05 hrs, 961 points
 Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
 Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

SubcatchmentP1: Proposed NW Runoff Area=10,395 sf 83.88% Impervious Runoff Depth=6.41"
 Tc=7.0 min CN=92 Runoff=2.38 cfs 5,553 cf

SubcatchmentP2: Proposed NE Runoff Area=12,683 sf 83.43% Impervious Runoff Depth=6.41"
 Tc=7.0 min CN=92 Runoff=2.91 cfs 6,775 cf

SubcatchmentP3: Proposed E Runoff Area=6,835 sf 89.69% Impervious Runoff Depth=6.65"
 Tc=7.0 min CN=94 Runoff=1.59 cfs 3,785 cf

SubcatchmentP4: Proposed SE Runoff Area=13,536 sf 82.93% Impervious Runoff Depth=6.41"
 Tc=7.0 min CN=92 Runoff=3.10 cfs 7,231 cf

SubcatchmentP5: Proposed SW Runoff Area=9,341 sf 96.58% Impervious Runoff Depth=7.00"
 Tc=7.0 min CN=97 Runoff=2.21 cfs 5,450 cf

SubcatchmentP6: Proposed Building Runoff Area=12,654 sf 100.00% Impervious Runoff Depth=7.12"
 Tc=10.0 min CN=98 Runoff=2.67 cfs 7,509 cf

SubcatchmentP7: Off-Site SW Runoff Area=6,455 sf 38.96% Impervious Runoff Depth=4.47"
 Tc=7.0 min CN=75 Runoff=1.14 cfs 2,403 cf

SubcatchmentP8: Off-Site E Runoff Area=1,272 sf 0.00% Impervious Runoff Depth=2.96"
 Tc=7.0 min CN=61 Runoff=0.15 cfs 314 cf

Pond 1P: Subsurface System Peak Elev=924.17' Storage=13,691 cf Inflow=14.77 cfs 36,303 cf
 Discarded=0.07 cfs 11,630 cf Primary=9.43 cfs 24,065 cf Secondary=0.00 cfs 0 cf Outflow=9.50 cfs 35,695 cf

Link 1L: SW Total Inflow=10.07 cfs 26,468 cf
 Primary=10.07 cfs 26,468 cf

Link 3L: E Total Inflow=0.15 cfs 314 cf
 Primary=0.15 cfs 314 cf

Total Runoff Area = 73,171 sf Runoff Volume = 39,021 cf Average Runoff Depth = 6.40"
16.84% Pervious = 12,324 sf 83.16% Impervious = 60,847 sf

22163 - Model

Prepared by Sambatek

HydroCAD® 10.00-20 s/n 01876 © 2017 HydroCAD Software Solutions LLC

MSE 24-hr 3 100-Year Rainfall=7.36"

Printed 7/24/2020

Page 37

Summary for Subcatchment P1: Proposed NW

Runoff = 2.38 cfs @ 12.14 hrs, Volume= 5,553 cf, Depth= 6.41"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-48.00 hrs, dt= 0.05 hrs
MSE 24-hr 3 100-Year Rainfall=7.36"

Area (sf)	CN	Description
1,676	61	>75% Grass cover, Good, HSG B
8,719	98	Paved parking, HSG B
10,395	92	Weighted Average
1,676		16.12% Pervious Area
8,719		83.88% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
7.0					Direct Entry,

Subcatchment P1: Proposed NW

Hydrograph



22163 - Model

Prepared by Sambatek

HydroCAD® 10.00-20 s/n 01876 © 2017 HydroCAD Software Solutions LLC

MSE 24-hr 3 100-Year Rainfall=7.36"

Printed 7/24/2020

Page 38

Summary for Subcatchment P2: Proposed NE

Runoff = 2.91 cfs @ 12.14 hrs, Volume= 6,775 cf, Depth= 6.41"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-48.00 hrs, dt= 0.05 hrs
MSE 24-hr 3 100-Year Rainfall=7.36"

Area (sf)	CN	Description
2,102	61	>75% Grass cover, Good, HSG B
10,581	98	Paved parking, HSG B
12,683	92	Weighted Average
2,102		16.57% Pervious Area
10,581		83.43% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
7.0					Direct Entry,

Subcatchment P2: Proposed NE

Hydrograph



22163 - Model

Prepared by Sambatek

HydroCAD® 10.00-20 s/n 01876 © 2017 HydroCAD Software Solutions LLC

MSE 24-hr 3 100-Year Rainfall=7.36"

Printed 7/24/2020

Page 39

Summary for Subcatchment P3: Proposed E

Runoff = 1.59 cfs @ 12.14 hrs, Volume= 3,785 cf, Depth= 6.65"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-48.00 hrs, dt= 0.05 hrs
MSE 24-hr 3 100-Year Rainfall=7.36"

Area (sf)	CN	Description
705	61	>75% Grass cover, Good, HSG B
6,130	98	Paved parking, HSG B
6,835	94	Weighted Average
705		10.31% Pervious Area
6,130		89.69% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
7.0					Direct Entry,

Subcatchment P3: Proposed E

Hydrograph



22163 - Model

Prepared by Sambatek

HydroCAD® 10.00-20 s/n 01876 © 2017 HydroCAD Software Solutions LLC

MSE 24-hr 3 100-Year Rainfall=7.36"

Printed 7/24/2020

Page 40

Summary for Subcatchment P4: Proposed SE

Runoff = 3.10 cfs @ 12.14 hrs, Volume= 7,231 cf, Depth= 6.41"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-48.00 hrs, dt= 0.05 hrs
MSE 24-hr 3 100-Year Rainfall=7.36"

Area (sf)	CN	Description
2,310	61	>75% Grass cover, Good, HSG B
11,226	98	Paved parking, HSG B
13,536	92	Weighted Average
2,310		17.07% Pervious Area
11,226		82.93% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
7.0					Direct Entry,

Subcatchment P4: Proposed SE

Hydrograph



22163 - Model

Prepared by Sambatek

HydroCAD® 10.00-20 s/n 01876 © 2017 HydroCAD Software Solutions LLC

MSE 24-hr 3 100-Year Rainfall=7.36"

Printed 7/24/2020

Page 41

Summary for Subcatchment P5: Proposed SW

Runoff = 2.21 cfs @ 12.14 hrs, Volume= 5,450 cf, Depth= 7.00"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-48.00 hrs, dt= 0.05 hrs
MSE 24-hr 3 100-Year Rainfall=7.36"

Area (sf)	CN	Description
319	61	>75% Grass cover, Good, HSG B
9,022	98	Paved parking, HSG B
9,341	97	Weighted Average
319		3.42% Pervious Area
9,022		96.58% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
7.0					Direct Entry,

Subcatchment P5: Proposed SW

Hydrograph



22163 - Model

Prepared by Sambatek

HydroCAD® 10.00-20 s/n 01876 © 2017 HydroCAD Software Solutions LLC

MSE 24-hr 3 100-Year Rainfall=7.36"

Printed 7/24/2020

Page 42

Summary for Subcatchment P6: Proposed Building

Runoff = 2.67 cfs @ 12.17 hrs, Volume= 7,509 cf, Depth= 7.12"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-48.00 hrs, dt= 0.05 hrs
MSE 24-hr 3 100-Year Rainfall=7.36"

Area (sf)	CN	Description
12,654	98	Paved parking, HSG B
12,654		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
10.0					Direct Entry,

Subcatchment P6: Proposed Building

Hydrograph



22163 - Model

Prepared by Sambatek

HydroCAD® 10.00-20 s/n 01876 © 2017 HydroCAD Software Solutions LLC

MSE 24-hr 3 100-Year Rainfall=7.36"

Printed 7/24/2020

Page 43

Summary for Subcatchment P7: Off-Site SW

Runoff = 1.14 cfs @ 12.14 hrs, Volume= 2,403 cf, Depth= 4.47"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-48.00 hrs, dt= 0.05 hrs
MSE 24-hr 3 100-Year Rainfall=7.36"

Area (sf)	CN	Description
3,940	61	>75% Grass cover, Good, HSG B
2,515	98	Paved parking, HSG B
6,455	75	Weighted Average
3,940		61.04% Pervious Area
2,515		38.96% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
7.0					Direct Entry,

Subcatchment P7: Off-Site SW

Hydrograph



22163 - Model

Prepared by Sambatek

HydroCAD® 10.00-20 s/n 01876 © 2017 HydroCAD Software Solutions LLC

MSE 24-hr 3 100-Year Rainfall=7.36"

Printed 7/24/2020

Page 44

Summary for Subcatchment P8: Off-Site E

Runoff = 0.15 cfs @ 12.15 hrs, Volume= 314 cf, Depth= 2.96"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-48.00 hrs, dt= 0.05 hrs
MSE 24-hr 3 100-Year Rainfall=7.36"

Area (sf)	CN	Description
1,272	61	>75% Grass cover, Good, HSG B
1,272		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
7.0					Direct Entry,

Subcatchment P8: Off-Site E

Hydrograph



22163 - Model

Prepared by Sambatek

HydroCAD® 10.00-20 s/n 01876 © 2017 HydroCAD Software Solutions LLC

MSE 24-hr 3 100-Year Rainfall=7.36"

Printed 7/24/2020

Page 45

Summary for Pond 1P: Subsurface System

Inflow Area = 65,444 sf, 89.13% Impervious, Inflow Depth = 6.66" for 100-Year event
 Inflow = 14.77 cfs @ 12.14 hrs, Volume= 36,303 cf
 Outflow = 9.50 cfs @ 12.24 hrs, Volume= 35,695 cf, Atten= 36%, Lag= 5.9 min
 Discarded = 0.07 cfs @ 6.35 hrs, Volume= 11,630 cf
 Primary = 9.43 cfs @ 12.24 hrs, Volume= 24,065 cf
 Secondary = 0.00 cfs @ 0.00 hrs, Volume= 0 cf

Routing by Stor-Ind method, Time Span= 0.00-48.00 hrs, dt= 0.05 hrs
 Peak Elev= 924.17' @ 12.24 hrs Surf.Area= 4,032 sf Storage= 13,691 cf

Plug-Flow detention time= 302.3 min calculated for 35,658 cf (98% of inflow)
 Center-of-Mass det. time= 293.6 min (1,050.4 - 756.8)

Volume	Invert	Avail.Storage	Storage Description
#1	925.25'	2,074 cf	Low Inlet Overflow (Prismatic) Listed below (Recalc)
#2A	918.50'	5,655 cf	29.92'W x 134.76'L x 5.50'H Field A 22,174 cf Overall - 8,036 cf Embedded = 14,138 cf x 40.0% Voids
#3A	919.25'	8,036 cf	ADS_StormTech MC-3500 d +Cap x 72 Inside #2 Effective Size= 70.4"W x 45.0"H => 15.33 sf x 7.17'L = 110.0 cf Overall Size= 77.0"W x 45.0"H x 7.50'L with 0.33' Overlap 4 Rows of 18 Chambers Cap Storage= +14.9 cf x 2 x 4 rows = 119.2 cf
		15,765 cf	Total Available Storage

Storage Group A created with Chamber Wizard

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
925.25	13	0	0
926.00	650	249	249
927.00	3,000	1,825	2,074

Device	Routing	Invert	Outlet Devices
#1	Primary	921.00'	15.0" Round Culvert L= 10.0' RCP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 921.00' / 920.96' S= 0.0040 ' S= 0.0040 ' Cc= 0.900 n= 0.013 Concrete pipe, bends & connections, Flow Area= 1.23 sf
#2	Discarded	918.50'	0.800 in/hr Exfiltration over Surface area
#3	Secondary	925.50'	10.0' long x 4.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.38 2.54 2.69 2.68 2.67 2.67 2.65 2.66 2.66 2.68 2.72 2.73 2.76 2.79 2.88 3.07 3.32

22163 - Model

Prepared by Sambatek

HydroCAD® 10.00-20 s/n 01876 © 2017 HydroCAD Software Solutions LLC

MSE 24-hr 3 100-Year Rainfall=7.36"

Printed 7/24/2020

Page 46

Discarded OutFlow Max=0.07 cfs @ 6.35 hrs HW=918.59' (Free Discharge)

↑**2=Exfiltration** (Exfiltration Controls 0.07 cfs)

Primary OutFlow Max=9.34 cfs @ 12.24 hrs HW=924.12' (Free Discharge)

↑**1=Culvert** (Inlet Controls 9.34 cfs @ 7.61 fps)

Secondary OutFlow Max=0.00 cfs @ 0.00 hrs HW=918.50' (Free Discharge)

↑**3=Broad-Crested Rectangular Weir** (Controls 0.00 cfs)

22163 - Model

Prepared by Sambatek

HydroCAD® 10.00-20 s/n 01876 © 2017 HydroCAD Software Solutions LLC

MSE 24-hr 3 100-Year Rainfall=7.36"

Printed 7/24/2020

Page 47

Pond 1P: Subsurface System - Chamber Wizard Field A

Chamber Model = ADS_StormTechMC-3500 d +Cap (ADS StormTech®MC-3500 d rev 03/14 with Cap volume)

Effective Size= 70.4"W x 45.0"H => 15.33 sf x 7.17'L = 110.0 cf

Overall Size= 77.0"W x 45.0"H x 7.50'L with 0.33' Overlap

Cap Storage= +14.9 cf x 2 x 4 rows = 119.2 cf

77.0" Wide + 9.0" Spacing = 86.0" C-C Row Spacing

18 Chambers/Row x 7.17' Long +1.85' Cap Length x 2 = 132.76' Row Length +12.0" End Stone x 2 = 134.76' Base Length

4 Rows x 77.0" Wide + 9.0" Spacing x 3 + 12.0" Side Stone x 2 = 29.92' Base Width

9.0" Base + 45.0" Chamber Height + 12.0" Cover = 5.50' Field Height

72 Chambers x 110.0 cf + 14.9 cf Cap Volume x 2 x 4 Rows = 8,035.7 cf Chamber Storage

22,173.6 cf Field - 8,035.7 cf Chambers = 14,137.9 cf Stone x 40.0% Voids = 5,655.2 cf Stone Storage

Chamber Storage + Stone Storage = 13,690.9 cf = 0.314 af


Overall Storage Efficiency = 61.7%

Overall System Size = 134.76' x 29.92' x 5.50'

72 Chambers

821.2 cy Field

523.6 cy Stone



22163 - Model

Prepared by Sambatek


HydroCAD® 10.00-20 s/n 01876 © 2017 HydroCAD Software Solutions LLC

MSE 24-hr 3 100-Year Rainfall=7.36"

Printed 7/24/2020

Page 48

Pond 1P: Subsurface System



22163 - Model

Prepared by Sambatek

HydroCAD® 10.00-20 s/n 01876 © 2017 HydroCAD Software Solutions LLC

MSE 24-hr 3 100-Year Rainfall=7.36"

Printed 7/24/2020

Page 49

Stage-Area-Storage for Pond 1P: Subsurface System

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
918.50	4,032	0	923.70	4,032	13,207
918.60	4,032	161	923.80	4,032	13,368
918.70	4,032	323	923.90	4,032	13,530
918.80	4,032	484	924.00	4,032	13,691
918.90	4,032	645	924.10	4,032	13,691
919.00	4,032	806	924.20	4,032	13,691
919.10	4,032	968	924.30	4,032	13,691
919.20	4,032	1,129	924.40	4,032	13,691
919.30	4,032	1,382	924.50	4,032	13,691
919.40	4,032	1,727	924.60	4,032	13,691
919.50	4,032	2,070	924.70	4,032	13,691
919.60	4,032	2,412	924.80	4,032	13,691
919.70	4,032	2,753	924.90	4,032	13,691
919.80	4,032	3,092	925.00	4,032	13,691
919.90	4,032	3,430	925.10	4,032	13,691
920.00	4,032	3,766	925.20	4,032	13,691
920.10	4,032	4,100	925.30	4,087	13,693
920.20	4,032	4,433	925.40	4,172	13,702
920.30	4,032	4,763	925.50	4,257	13,721
920.40	4,032	5,092	925.60	4,342	13,747
920.50	4,032	5,418	925.70	4,427	13,783
920.60	4,032	5,742	925.80	4,512	13,827
920.70	4,032	6,063	925.90	4,597	13,879
920.80	4,032	6,382	926.00	4,682	13,940
920.90	4,032	6,698	926.10	4,917	14,016
921.00	4,032	7,010	926.20	5,152	14,117
921.10	4,032	7,320	926.30	5,387	14,240
921.20	4,032	7,626	926.40	5,622	14,388
921.30	4,032	7,929	926.50	5,857	14,558
921.40	4,032	8,228	926.60	6,092	14,753
921.50	4,032	8,523	926.70	6,327	14,970
921.60	4,032	8,813	926.80	6,562	15,212
921.70	4,032	9,098	926.90	6,797	15,476
921.80	4,032	9,379	927.00	7,032	15,765
921.90	4,032	9,654			
922.00	4,032	9,923			
922.10	4,032	10,186			
922.20	4,032	10,441			
922.30	4,032	10,689			
922.40	4,032	10,927			
922.50	4,032	11,154			
922.60	4,032	11,366			
922.70	4,032	11,560			
922.80	4,032	11,740			
922.90	4,032	11,913			
923.00	4,032	12,078			
923.10	4,032	12,240			
923.20	4,032	12,401			
923.30	4,032	12,562			
923.40	4,032	12,723			
923.50	4,032	12,885			
923.60	4,032	13,046			

22163 - Model

Prepared by Sambatek

HydroCAD® 10.00-20 s/n 01876 © 2017 HydroCAD Software Solutions LLC

MSE 24-hr 3 100-Year Rainfall=7.36"

Printed 7/24/2020

Page 50


Summary for Link 1L: SW Total

Inflow Area = 71,899 sf, 84.63% Impervious, Inflow Depth = 4.42" for 100-Year event
Inflow = 10.07 cfs @ 12.23 hrs, Volume= 26,468 cf
Primary = 10.07 cfs @ 12.23 hrs, Volume= 26,468 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-48.00 hrs, dt= 0.05 hrs

Link 1L: SW Total

Hydrograph



22163 - Model

Prepared by Sambatek

HydroCAD® 10.00-20 s/n 01876 © 2017 HydroCAD Software Solutions LLC

MSE 24-hr 3 100-Year Rainfall=7.36"

Printed 7/24/2020

Page 51


Summary for Link 3L: E Total

Inflow Area = 1,272 sf, 0.00% Impervious, Inflow Depth = 2.96" for 100-Year event
Inflow = 0.15 cfs @ 12.15 hrs, Volume= 314 cf
Primary = 0.15 cfs @ 12.15 hrs, Volume= 314 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-48.00 hrs, dt= 0.05 hrs

Link 3L: E Total

Hydrograph



APPENDIX D – MIDS Calculations

Project Information

Calculator Version:	Version 3: January 2017
Project Name:	Woodspring Suites Hotel
User Name / Company Name:	Sambatek
Date:	7/24/2020
Project Description:	The proposed project consists of the development of a 2.04-acre site located at 1744 County Road D in Maplewood, Ramsey County, Minnesota. The site is within the Ramsey-Washington Metro Watershed District. The proposed site consists of the construction of a 4-story Hotel and adjacent parking lots.
Construction Permit?:	Yes

Site Information

Retention Requirement (inches):	1.1
Site's Zip Code:	55109
Annual Rainfall (inches):	32
Phosphorus EMC (mg/l):	0.3
TSS EMC (mg/l):	54.5

Total Site Area

Land Cover	A Soils (acres)	B Soils (acres)	C Soils (acres)	D Soils (acres)	Total (acres)
Forest/Open Space - Undisturbed, protected forest/open space or reforested land					0
Managed Turf - disturbed, graded for yards or other turf to be mowed/managed	.17				0.17
			Impervious Area (acres)		1.33
			Total Area (acres)		1.5

Site Areas Routed to BMPs

Land Cover	A Soils (acres)	B Soils (acres)	C Soils (acres)	D Soils (acres)	Total (acres)
Forest/Open Space - Undisturbed, protected forest/open space or reforested land					0
Managed Turf - disturbed, graded for yards or other turf to be mowed/managed	0.17				0.17
			Impervious Area (acres)		1.33
			Total Area (acres)		1.5

Summary Information

Performance Goal Requirement

Performance goal volume retention requirement:	5311	ft ³
Volume removed by BMPs towards performance goal:	5311	ft ³
Percent volume removed towards performance goal	100	%

Annual Volume and Pollutant Load Reductions

Post development annual runoff volume	3.0936	acre-ft
Annual runoff volume removed by BMPs:	3.003	acre-ft
Percent annual runoff volume removed:	97	%

Post development annual particulate P load:	1.388	lbs
Annual particulate P removed by BMPs:	1.348	lbs
Post development annual dissolved P load:	1.136	lbs
Annual dissolved P removed by BMPs:	1.103	lbs
Percent annual total phosphorus removed:	97	%

Post development annual TSS load:	458.6	lbs
Annual TSS removed by BMPs:	445.2	lbs
Percent annual TSS removed:	97	%

BMP Summary

Performance Goal Summary

BMP Name	BMP Volume Capacity (ft ³)	Volume Recieved (ft ³)	Volume Retained (ft ³)	Volume Outflow (ft ³)	Percent Retained (%)
1 - Underground infiltration	7010	5311	5311	0	100

Annual Volume Summary

BMP Name	Volume From Direct Watershed (acre-ft)	Volume From Upstream BMPs (acre-ft)	Volume Retained (acre-ft)	Volume outflow (acre-ft)	Percent Retained (%)
1 - Underground infiltration	3.0936	0	3.003	0.0905999999	97

Particulate Phosphorus Summary

BMP Name	Load From Direct Watershed (lbs)	Load From Upstream BMPs (lbs)	Load Retained (lbs)	Outflow Load (lbs)	Percent Retained (%)
1 - Underground infiltration	1.3884	0	1.3478	0.0406	97

Dissolved Phosphorus Summary

BMP Name	Load From Direct Watershed (lbs)	Load From Upstream BMPs (lbs)	Load Retained (lbs)	Outflow Load (lbs)	Percent Retained (%)
1 - Underground infiltration	1.136	0	1.1027	0.0333	97

TSS Summary

BMP Name	Load From Direct Watershed (lbs)	Load From Upstream BMPs (lbs)	Load Retained (lbs)	Outflow Load (lbs)	Percent Retained (%)
1 - Underground infiltration	458.6	0	445.17	13.43	97

BMP Schematic

